ONESTEP POWER SOLUTIONS INC.

We Stop Blackouts.

DP Shuttle Tankers 2024



OUR MISSION

Independent assurance to accelerate the future of clean power.

OUR VALUES

Safe Solutions
Technical Excellence
Trusted Service



INTRODUCTION TO ONESTEP POWER

Independent validation & verification to help you:

- **STOP BLACKOUTS**: Ensure operational safety
- **GO GREEN**: Simplify the energy transition
- 3. **GET ON CONTRACT**: Get to work, fast

An integrated, technology-based approach to Verification & Validation of power technologies.











CONTROL SYSTEM CROSS CONNECTIONS - DEFINED

- Control system cross-connections exist as part of increased reliability on DP control system.
- 2. The opportunities for single failures decreased.








CROSS CONNECTIONS - THE RISK

- 1. Traditional isolation methods:
 - a. Risk of low likelihood, high severity failures.
 - b. Diodes do not eliminate voltage dip.
- 2. Modern power supplies may not supply sufficient fault current.
- 3. Adding more power supplies takes space, time and money.





CROSS-CONNECTIONS


DP Shuttle Tankers

- **★** Client-driven requirements
 - Matched to OCIMF, Shell & Petrobras cross-connection testing requirements
- ★ Quick
 - Generally 2-3 days onboard
 - Can perform in Transit (on DP)
- ★ Data-driven
 - Automated assessment of results
- ★ Reduces isolation checklists



ONESTEP POWER'S DCSHORTCUT

- Temporary Installation
- Keeps personnel clear of testing
- Repeatable tests
- Clear pass/fail criteria
- Vessel protections remain "as-is"
- Invisible to the vessel
- Responses are real fault responses





ONESTEP POWER'S DCSHORTCUT

DCShortCUT Failure Mode Matrix	Downstream of PSU1	Downstream of PSU2	Downstream of PSU1 & PSU2 simultaneously	Between protections & load
Load Increase	*	*		*
Overload	*	*		*
Short Circuit	*	*	*	*
Short to Ground / Earth Fault	*	*	*	*
Variable over-voltage (max 120%)	*	*		*
Loss of Power Supply	@ PSU1	@ PSU2		





WHAT IS THE PROCESS?

ShortCUT Projects

Plan

Test

Report

Design & verify test plan.

Mobilize testing personnel and equipment.

10 business days.

Temporary installation of test kit.

Immediate test results.

2 person verification.

2-4 days, on DP (while in transit is ok).

De-mobilize testing personnel and equipment.

Full Report.

10 business days.



AFTER THE FINAL REPORT

Additional Support

- Contract Acceptance Support
- Power & Alarm Monitoring
- Power Engineering Support
 - Updates to manuals
 - Answering Charterer questions
 - Closed bus workshops & risk assessments
- Incident Investigation
- Annual Power System Reviews





THANK YOU!

info@onesteppower.com

www.onesteppower.com







